Overall Dimensions Installation В Be sure to leave enough space between the footings and the fire ring so that it can be flipped up for cleaning purposes. Estimated Required Concrete: 3 - 50lb Bags of Concrete Mix Attach the ground staples to the Fire Ring before inserting then into the concrete footings. Ground Staples are included. 1. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
2. ALL DIMENSIONS APE CONSIDERED TRUE AND PEFLECT MANUFACTURER'S SPECIFICATIONS.
3. DO NOI SCALE DRAWING. **OCC Outdoors Products** PH: 1-800-821-7670 EMAIL - occcontact@occoutdoors.com This document contains OCC Outdoors Proprietary Information. No intellectual copyright or Fax: 1-317-862-9422 license is granted by OCC Outdoors in connection with it. It is delivered on the express condition that the document and the information contained in it shall be treated as confidential, shall not be Part #: OCC-600-9 9" High Fire Ring with Grate used for and purpose other than that for which it is hereby delivered (the use and maintenance of the product supplied). It shall not be disclosed in whole or part to third parties and shall not be Date: 8/05/2015 duplicated in any manner without OCC Outdoors's prior approval.